HEADQUARTER RANGE, MYSORE.

Abstract Notification.

Reference is invited to the notification calling for tenders for the construction of South Fort Gate with wings at Mysore, published in pages 1002—1003 of the *Mysore Gazette*, dated 14th November 1918.

GURU RAO SIRSI,
Assistant Engineer.

MYSORE DIVISION.

Dated 13th November 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 5th December 1918, for improving the 2nd Class Travellers' bungalow at Somanahalli, Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the 2nd Class travellers' bungalow at Somanahalli, Mandya Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever, for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of sanctioned quantities with units for improving the 2nd class travellers' bungalow at Somanahalli, Mandya Taluk.

Items of work	Per	Quantity
Main building.		
1. Dismantling the existing Bengal terrace and re-roofing with Mangalore tiles set in mortar over the existing reepers with flat tiles.	Sq.	31·50
2. Mangalore ridge tiles set in mortar	R. ft.	68
3. Converting the side pials into bath room, brick in chunam	C. ft.	90
4. Chunam plastering	Sq.	1·75
5. Burnt stone slabs dressed and fixed	S. ft.	46
6. Removing the window and refixing the door	Lump	sum
7. Teakwood ventilators with iron bars and glazed shutters	S. ft.	7
8. Painting	Sq.	2·46
9. Flooring with 1st class Mangalore tiles on 3" concrete bed and cement pointed, complete.	"	6·53
10. Teakwood panelled door including frames and hinges, etc., complete	S. ft.	91
11. Teakwood work wrought and put up	C. ft.	16
12. Stone brackets including cutting	No.	14
13. Mending the sagged rafters and fixing the same...	Lump	sum
Native Kitchen.		
14. Flooring with 1st class Mangalore tiles on mortar bed and cement pointed ...	Sq.	2·82
15. Flooring with Cuddappah slabs on mortar bed and cement pointed ...	"	1·40
16. Removing the existing plastering	"	2·82
17. Providing wooden pegs including nails	Each	12
18. Lever locks	No.	1
19. Ventilating tiles	"	4
20. Constructing sinks in bath room	Lump	sum
21. Constructing surki concrete drain	R. ft.	50
22. Providing wire gauge	"	6
European Kitchen.		
23. Removing the old roofing and stocking	Sq.	12·88
24. Roofing with 1st class Mangalore tiles on teak reepers, etc., complete ...	"	12·88
25. Mangalore ridge tiles set in mortar and cement pointed	S. ft.	46
26. Providing iron bars to windows	...	95
Stables.		
27. Dismantling old masonry and removing to a distance	C. ft.	4·7
28 Burnt stone slabs dressed and fixed	S. ft.	166
29. Burnt stone in chunam	C. ft.	313
30. Chunam plastering	Sq.	3·33
31. Earthwork excavation	Lump	sum
32. Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	Sq.	12·88
33. Removing old roof and stocking serviceable materials ...	"	12·88
34. White and colourwashing	"	21·48
35. Teakwood work in place of old and unserviceable	Lump	sum

A. PUTTUSWAMIAH, *Executive Engineer.*